

Installation of *SolarVenti Industrial*



The system is delivered in parts to minimize costs. Approx 60 m² can be shipped on 1 pallet.

- 1) assemble the frame (not shown here)
- 2) mount the back plate into the frame

Assembling of the parts



One man can easily carry an element. Mounting can be done by 1 man.





Rubber band between the elements.

